

LAKE CITY 10 Marla House

SUBJECT : Cement Sand Mortar (1:4) Bed Plaster 1.5" thick

Sr No	Area	Qty	Unit	Remarks
	Basement Servant	108		
	Ground Floor Garrage Area	305		
	Ground Floor Lobby 5' Wide	219		
	Ground Floor Passage 7' Wide	153		
	TOTAL	785	Sft	

Material Resources

Cement 26 Bags
Sand 96 Cft