

**CMPAK - BLOCK B**  
**RESOURCES FOR FLOORING WORKS**

Description	Qty	Unit	Cement (Bags)	Sand (Cft)	Crush (Cft)	Ghassu (Cft)	Remarks
<b>Basement Floor</b>							
Ghassu Filling	28,125	Cft				28,125	2'3" + 3"
Pcc 1:4:8 3" Thick	2,500	Cft	237	1,185	2,370		
RCC Floor 9" Thick	7,500	Cft	1,358	4,053	6,401		
PCC 1:2:4 4" Thick	3,333	Cft	587	1,467	2,933		
<b>Ground Floor</b>							
PCC 1:2:4 4" Thick	3,333	Cft	587	1,467	2,933		
<b>1st Floor</b>							
PCC 1:2:4 4" Thick	3,333	Cft	587	1,467	2,933		
<b>2nd Floor</b>							
PCC 1:2:4 4" Thick	3,333	Cft	587	1,467	2,933		
<b>3rd Floor</b>							
PCC 1:2:4 4" Thick	3,333	Cft	587	1,467	2,933		
<b>TOTAL</b>			<b>4,529</b>	<b>12,572</b>	<b>23,437</b>	<b>28,125</b>	